



ROOF FRAMING – SLOPED ROOF

1. 2"x4" RAFTERS AT 16" O/C W/ 3/8" PLYWOOD SHEATING
2. 2"x4" RAFTERS AT 24" W/ 3/8" PLYWOOD SHEATING AND H-CLIPS.

MEMBER SIZE	ROOF SNOW LOAD 21 PSF			ROOF SNOW LOAD 31 PSF		
	ROOF JOIST SPACING			ROOF JOIST SPACING		
	12"	16"	24"	12"	16"	24"
2x6	12'-9"	11'-7"	10'-1"	11'-2"	10'-1"	8'-10"
2x8	16'-9"	15'-3"	13'-3"	14'-7"	13'-3"	11'-7"
2x10	21'-1"	19'-5"	17'-0"	18'-8"	17'-0"	14'-10"
2x12	26'-1"	23'-8"	20'-8"	22'-9"	20'-8"	18'-0"

NOTES:

1. ALL LUMBER TO BE NO. 2 SPRUCE OR BETTER.
2. ALL PLYWOOD TO BE STAMPED "APPROVED EXTERIOR GRADE".
3. EXTERIOR FINISH TO GARBAGE BIN ENCLOSURE TO MATCH EXTERIOR FINISH ON PROPOSED BUILDING.

ALL DIMENSIONS IN MILLIMETRES EXCEPT WHERE NOTED

THE CORPORATION OF THE TOWN OF WHITBY

PUBLIC WORKS DEPARTMENT

CHECKED: *AB*
 APPROVED: *AB*
 SCALE: N.T.S

**GARBAGE BIN ENCLOSURE WITH ROOF
 TABLES AND NOTES**

DWG. DATE: MAY 2006
 REVISION No.: 1
 REVISION DATE: JULY 2011
 DWG No. 507.20